CHITALDROOG DIVISION.

[ADVERTISEMENT.

The 17th July 1895.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Chitaldrug Division, up to 31st August 1895, for constructing a new tank near Mustalgummi, Challakere Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1897.

2. The plans, detailed estimate, and conditions may be seen at the Executive Engineer's Office at Chitaldrug between the hours of 11 A. M. and 4 P. M. on office days.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 100 in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for constructing a new tank near Mustalgummi, Challakere Taluk," in default of which tenders will be rejected.

5. The final acceptance of any tender will rest with the Chief Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within 8 days of the acceptance of the tender the successful competitor will be required to execute the usual contract bond, in default of which his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor whose tender has been accepted will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders the earnest money on rejected tenders will be returned.

Items of work.	*Per.*	*Quantity.*
Bund—		
Earthwork (special)	C. yd.	31,919
Clay puddling	"	2,382
Clearing silt	"	,002
Cutting jungle	L. S.	
New stone work	C. yd.	2,296
Grade stones	No.	20
B. M. stones	No.	2
Gauge stone	No.	1
Tank No. stone	No.	1
Turfing	S. yd.	6,790
Total..		
Sluice Nos. 1 *&* 2—		
Brick in ordinary mortar	C. ft.	2,538
Burnt stone slabs dressed	S. ft.	68
Ditto undressed	"	570
Plastering with mortar	Sqr.	9·96
Earthwork	C. yd.	270
Gibbet stones dressed	No.	4
Total for 2 sluices..		
Waste Weir—		
Brick in mortar	C. ft.	1,055
Burnt stone slabs dressed	S. ft.	225
Ditto undressed	"	366
Rough stone work	C. yd.	40
Ditto Sujicut	"	270
Earthwork	"	589
Plastering with mortar	Sqr.	11·61
Total..		

K. PRAHALNADA RAO, *Offg. Executive Engineer.*

EDUCATION DEPARTMENT.

NOTIFICATION.

The 17th July 1895.

D. No. 5.

The Kannada Pandits' Examination.

1. An Examination called "the Kannada Pandits' Examination" will be held annually at Mysore on the 1st December and following days. The first Examination will be held in December 1895.

2. The Examination will be open only to those who have passed the Vernacular Teachers' or Upper Secondary Examination, or the Matriculation Examination of the Madras University, at least two years previous to the date of the Pandits' Examination at which they intend to appear.

3. Applications for admission to this Examination must reach the Manager of the Mysore Local Examinations, Bangalore, not later than the 31st August. Each candidate shall forward with his application the certificate of having passed the Vernacular Teachers' or Upper Secondary Examination, or the Matriculation Examination of the Madras University.